

INDUSTRIA QUÍMICA DEL ISTMO S.A. de C.V.

# CloroSur 2022

COSTA DO SAUÍPE

# "Mercury Plants Remediation experiences and next steps"

November 2022

## CYDSA S.A. de C.V.





Sales del Istmo

Produce y comercializa sal yodada y fluorurada para el consumo Elabora y comercializa cloro, sosa cáustica y especialidades químicas

**IQUISA** 



**Quimobásicos** Fabrica y distribuye gases refrigerantes, propelentes y



Cogeneración de Electricidad y Vapor Genera y comercializa energía



Procesamiento y Almacenamiento Subterráneo de Hidrocarburos

#### 1. Monterrey, Nuevo León

- 2. Coatzacoalcos, Veracruz
- 3. García, Nuevo León
- 4. Ecatepec, Estado de México
- 5. San Cosme Xalostoc, Tlaxcala
- 6. Hermosillo, Sonora
- 7. Ixhuatlán del Sureste, Veracruz
- 8. Ciudad de México

# Cydes 1 Our Company

CYDSA's five business areas include: Salt for Household Consumption and Industrial Applications; Chlorine, Caustic Soda and Related Specialties; Electricity and Steam Cogeneration; and Hydrocarbons Processing and Underground Storage. Headquartered in Monterrey, Mexico, the Company incorporates more than 20 subsidiaries located in 8 cities and serves customers in more than 15 countries.



### Industria Química del Istmo S. A. de C.V.





## Industria Química del Istmo S. A. de C.V.







| PLANT             |           |             |
|-------------------|-----------|-------------|
| SANTA CLARA       | $\otimes$ | 2007        |
| MONTERREY/NORESTE | $\otimes$ | <b>2016</b> |
| COATZACOALCOS     | $\otimes$ | 2023        |

#### CHLORINE CAUSTIC SODA PRODUCTION TECHNOLOGIES.



Mercury



Membrane



## **IQUISA Mercury Plants Cell Area Remediation**

| PLANTo        | STATUS       | YEAR           | Hg INVENTORY (TONS) |
|---------------|--------------|----------------|---------------------|
| SANTA CLARA   | $\checkmark$ | Concluded 2014 | No Inventory        |
| MONTERREY     | Х            | Pending        | No Inventory        |
| COATZACOALCOS | Х            | Pending        | 150                 |



In 1958, it formally began operations with a De Nora mercury electrolysis process.

In 1966, an extension to the Chlorine process was carried out with the installation of Olin Mathieson technology cell mercury technology.

In 1974 Olin mercury cells were installed and the capacity of the plant was increased to 100 tons/day of chlorine.

On August 31, 2007, the production of chlorine began with the new membrane technology, allowing lower energy consumption, low production and maintenance costs, as well as a friendlier relationship with the environment by ceasing to use mercury. Finally, the Mercury Technology electrolysis plant suspended activities after 50 years of operation.

The objective of the "Environmental Remediation of the area occupied by the Ex-Electrolysis plant", consisted in the release of the environmental liability through the execution of activities detailed until the remaining soil and subsoil at surface level at depths greater than 6 m is below the Maximum Permitted Limits established in NOM-147-SEMARNAT/SSA1-2004, of, 310 mg/kg."



The area and depth of the excavation. It was at the end of 3,613.54 m<sup>2</sup>, equivalent, the average depth of the excavation was 8.4 meters and there were areas where the excavation extended up to the 15 meters.



Based on the guidelines of the Safety, Health and Environmental Program, different work areas were determined for the execution of Remediation, which were identified and delimited.

#### NOMENCLATURE

| 1 | Hazardous waste area           |
|---|--------------------------------|
| 2 | Unit decontamination           |
| 3 | Personnel decontamination      |
| 4 | Stock materials                |
| 5 | mobile toilets                 |
| 6 | hydration area                 |
| 7 | Dining room and dressing rooms |
| 8 | Mobile office camp             |
| 9 | staff showers                  |



#### **RECOVERY OF LIQUID MERCURY**

The visual inspection and mercury aspiration was carried out mainly at the beginning of the Remediation in October 2012 and concluded in August 2013, however the equipment was available to the operational area throughout the activities carried out. The total volume of mercury recovered during this activity was approximately 297.25 kg.





The physical remediation process was completed in a 24-month period from October 2012 to 2014.

All the guidelines, conditions and provisions required by SEMARNAT were complied with, with which we were authorized to remediate the site.

The applicable regulations in force were complied with.

The total cost of the remediation was of the order of 100 million pesos (7 MM USD), impacted in large part by the freight costs of shipments to confinement of RESIDUOS INDUSTRIALES MULTIQUIM (RIMSA) in Mina N.L.



# **IQUISA MONTERREY /COATZACOALCOS REMEDIATION**







#### FIRST STAGE MONTERREY PLANT.

For the Remediation of the Monterrey Plant, to decontaminate the soil and materials will be using, in a Pilot Test, Equipment from the German Company

#### **ECON INDUSTRIES:** ECON VacuDry 3000 evaporation unit.

Once the land and materials have been decontaminated and already complying with the maximum parameters of the current regulations of the Mercury content for soils,

All this material will be recovered/reused to refill the area where it was extracted.

During this soil operation decontamination Liquid Mercury will be generated, which will be stabilized with Sulfur to form the compound HgS (CINABRIO) which is considered an inert material for special handling and will be stored in authorized places. To carry out this operation, equipment of the German company ECON INDUSTRIES will be used:

**ECON Modelo 150**.



#### **Mercury Remediation**

On-site treatment. Decontamination of Material and Backfill; Thermal decomposition of mercurycontaminated material in a Pilot Test with the ECON VacuDry 3000 evaporation unit, operating under vacuum, for the recovery of Water and Mercury, decontaminating the material and allowing it to be reused for filling the area to be decontaminated.

TECNÓLOGY. ECON INDUSTRIES (ALEMANIA).



#### **EQUIPMENT (Skid Mounted)**

Capacidad del equipo; 16.5 Ton/día de material contaminado. Operación Total con Energía Eléctrica; Energía Eléctrica/Diesel.

#### TIME EXECUTION.

-Monterrey; 3 Yerars (15,000 Tons), Coatzacoalcos; 4 Years (20,000 Tons).

-BUDGET; \$ US MM. Equipment Cost: 3,600,000. (





#### Mercury Stabilization.

ON-SITE TREATMENT OF 100 TONS OF MERCURY WITH ECON MODEL 150 PROCESS EQUIPMENT; To carry out a pilot test for its stabilization by chemical reaction with Sulfur(S), to form Mercury Sulfide (HgS, CINABRIO) and its disposal as a Management Waste special in a Collection Center of the Region

TECHNÓLOGY. ECON INDUSTRIES (GERMANY).





#### **EQUIPMENT (Mobile Unit)**

Capacidad del equipo; 200 Kgs. Hg/Batch (600 Kgs. Hg /día). Operación Total con Energía Eléctrica.

EXECUTION TIME.

-1 Year.

-BUDGET (\$ US MM). EQUIPMENT COST: 990,000.



#### SECOND STAGE COATZACOALCOS PLANT;

It consists of the stabilization of 100 Tons of Mercury Product of the Decommissioning of the Electrolytic Cells of the Coatzacoalcos Plant,

To carry out this operation, the aforementioned Equipment of the German Company ECON INDUSTRIES will be used in a Pilot Test:

ECON Modelo 150.



#### THIRD STAGE COATZACOALCOS PLANT;

For the Remediation of the Coatzacoalcos Plant, it is proposed to decontaminate the land and materials, using in a Pilot Test Equipment from the German Company ECON INDUSTRIES

**ECON VacuDry 3000 evaporation unit.** 

Once the land and materials have been decontaminated and already complying with the maximum parameters of the Mercury content of the current Regulations for soils, it will be reused to fill the area where it was extracted. During this operation, liquid Mercury will be generated, which will be stabilized with Sulfur to form the compound HgS (CINABRIO), which is considered an inert material for special handling and will be stored in authorized places. To carry out this operation, a Pilot Test Equipment from the German Company ECON INDUSTRIES will be used:

ECON Model 150 .



## **Monterrey Plant Remediation Schedule Phase I**

| Plan para Eliminar el uso del mercurio γ manejar   |    | AÑ | 01      |   |    | AN | 32 |   |   | AN | <b>a</b> |   |   |   | 04 |   |    | AN | 2.5 |   |
|--|----|----|---------|---|----|----|----|---|---|----|----------|---|---|---|----|---|----|----|-----|---|
| adecuadamente el mercurio y sus residuos en el<br>sector Cloro-Alcali en México.   | 11 | n  | 1       | = | 11 | n  | 11 | Ħ | = | n  | 11       | н | = | ñ | =  | н | 11 | п  | =   | = |
| EQUIPO ECON INDUSTRIES   |    |    | · · · · |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Equipos ECON VacuDry 3000 evaporation unit y<br>Modelo 150 para recuperar mercurio de<br>material contaminado y estabilizar mercurio |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Compra del Equipo  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Transportación   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| PLANTA MONTERREY   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Decommisioning   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Desinstalar Equipo Eléctrico periferico  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Desmantelar Equipo periferico Area de Celdas   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Demanmtelar y descontaminación de techo de celdas  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Desmontar y descontaminar Estructura edificio  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Desmontar y descontaminar Equipo y tuberías  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Demoler y Descontaminar Nivel de Piso de Celdas<br>Demoler y descontaminar Concreto de Piso planta bajar de<br>Celdae                |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| INSTALACION EQUIPO ECON INDUSTRIES   |    |    | · ·     |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Instalacion Equipo ECDN VacuDry 3000 evaporation unit  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Instalacion Equipo Modelo 150  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Capacitación y Puesta en Marcha  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| DESCONTAMINACIÓN DE TIERRA   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Plan de Muestreo y Analísis  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Muestreo y Analisis (Continuo)   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Retiro de tierra y descontaminacion  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Establización de Hg recuperado de la tierra contaminada con EQUIPO<br>ECON 150   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Almacenamiento de tierra decontaminada   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Relleno con tierra descontaminada  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Muestreo Final   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Lozaa de Concreto Final (Conclusión)   |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |
| Reporte Final  |    |    |         |   |    |    |    |   |   |    |          |   |   |   |    |   |    |    |     |   |



#### **Coatzacoalcos Plant Stabilization Schedule Phase II**

|  |    | AÑO | 1        |    | AÑ | 02 |    |    | AÑO | 3  |    |    | AÑO | 04 |    |    | AÑO | 5  |     |    | AÑC | 06 |     |
|--|----|-----|----------|----|----|----|----|----|-----|----|----|----|-----|----|----|----|-----|----|-----|----|-----|----|-----|
| Plan para Eliminar el uso del mercurio y manejar<br>adecuadamente el mercurio y sus residuos en el<br>sector Cloro-Alcali en México. | 11 | 12  | T3<br>T4 | 11 | T2 | T3 | T4 | 11 | 72  | 13 | 74 | 71 | 12  | T3 | T4 | 11 | 12  | 13 | T.4 | 11 | T 2 | T3 | T 4 |
| PLANTA COATZACOALCOS   |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| ESTABILIZACION DE MERCURO RECUPERADO DE CELDAS   |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Instalacion Equipo Modelo 150  |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Capacitación y Puesta en Marcha  |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Recuperación de 50Tomeadas de Mercurio de celdas   |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Envio de Mercurio a Plantas de Sudamerica  |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Recuperación de 100 Tomeadas de Mercurio de cel das  |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Estabilización de Mercurio Y confinamiento Na2 S   |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |
| Reporte Final  |    |     |          |    |    |    |    |    |     |    |    |    |     |    |    |    |     |    |     |    |     |    |     |



#### **Coatzacoalcos Plant Remedaition Schedule Phase III**

| Plan para Eliminar el uso del mercurio y manejar                               |    | AÑ | 01 |    |    | AÑC | 02 |    |    | AÑO | 3 |    |    | AÑO | 54 |    |    | AÑ | 0 5 |    |    | AÑ  | 06 |    |    | AÑ | 10 7 |    |    | AÑ | 08 |    |    | AÑO | 9  |    |           | AÑO           | 10 |    |    | AÑO : | 11 |    |    | AÑO 1  | 12        |    |
|--|----|----|----|----|----|-----|----|----|----|-----|---|----|----|-----|----|----|----|----|-----|----|----|-----|----|----|----|----|------|----|----|----|----|----|----|-----|----|----|-----------|---------------|----|----|----|-------|----|----|----|--------|-----------|----|
| adecuadamente el mercurio y sus residuos en el sector Cloro-Alcali en México.  | Τ1 | 11 | E  | T4 | Τ1 | 12  | T3 | T4 | τ1 | 12  | £ | T4 | τ1 | 21  | щ  | T4 | Τ1 | Τ2 | Т3  | Τ4 | τ1 | Т 2 | Т3 | Τ4 | Τ1 | Τ2 | Τ3   | Τ4 | T1 | τ2 | Т3 | Τ4 | τ1 | Τ2  | Т3 | Τ4 | Τ1        | Т2            | Т3 | Τ4 | T1 | Τ2    | T3 | Τ4 | T1 | Τ2     | Т3        | Τ4 |
| PLANTA COATZACOALCOS   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| INSTALACION EQUIPO VACCUM DRY ECON INDUSTRIES                                  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Instalacion Equipo ECON VacuDry 3000 evaporation unit                          |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Capacitación y Puesta en Marcha  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Decommisioning   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Desinstalar Equipo Eléctrico periferico  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Desmantelar Equipo periferico Area de Celdas                                   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Demanmtelar y descontaminación de techo de celdas                              |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Desmontar y descontaminar Estructura edificio                                  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Desmontar y descontaminar Equipo y tuberías                                    |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Demoler y Descontaminar Nivel de Piso de Celdas                                |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    | $\square$ | $\square$     |    |    |    | _     |    |    |    | $\bot$ | $\square$ |    |
| Demoler y descontaminar Concreto de Planta Baja de Celdas                      |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    | _         | $\rightarrow$ |    |    |    | +     |    |    |    | +      | +         |    |
| DESCONTAMINACIÓN DE TIERRA   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Plan de Muestreo y Analisis  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Muestreo y Analisis (Continuo)   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Retiro de tierra y descontaminacion  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Establización de Hg recuperado de la tierra contaminada con EQUIPO<br>ECON 150 |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Almacenamiento de tierra decontaminada   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Relleno con tierra descontaminada  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Muestreo Final   |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |
| Loza de Concreto Final (Conclusión)  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    | -      |           |    |
| Reporte Final  |    |    |    |    |    |     |    |    |    |     |   |    |    |     |    |    |    |    |     |    |    |     |    |    |    |    |      |    |    |    |    |    |    |     |    |    |           |               |    |    |    |       |    |    |    |        |           |    |



#### **GEF FUNDS**.

IQUISA as a producer of Chlorine with Mercury Technology and Mexico as a signatory country of the Minamata Agreement on October 10, 2013 and ratified on September 29, 2015.

And also signed by 128 countries and ratified by 131 countries. The Convention entered into force in August 2017, as a legally binding instrument, whose objective is:

"To protect human health and the environment from anthropogenic releases of mercury and mercury compounds".

In which it establishes that:

--Annex B part I; Manufacture of chlorine soda using mercury should be suspended by 2025.

-Article 3 paragraph 5b; Stabilize and adequately dispose of the excess mercury left over from the operation of the plants.

-Article 12; Environmentally sound management of sites contaminated with Mercury as a result of operation.

#### **GEF FUNDS**.

Since 2010 IQUISA's Team have participated in the forums and events organized by UNEP( United Nations Environmental Program). Looking for :

-Support for Remediation of sites contaminated with Mercury as a result of the operation.

-Support for Mercury conversion project to membrane Technology.



In COP 1 was defined that GEF( Global Environmental Facility) will destinate support resources for finance projects for developing countries to comply with Minamata Covention.

#### (\*1) INC'S Intergovernmental Negotiating Committee

#### **GEF FUNDS**.

Process to get GEF funds is a long Journey, according with their policies and protocols and documents requirements, it is necessary to prepare, fullfill and submit applications information and also executing field monitoring in the sites to be remediated.

#### With next roadmap process:



### **GEF BUDGET \$ US**.



M.Sc. Carlos Manuel Rodriguez CEO and Chairperson

April 29, 2022

Ms. Victoria Luque GEF Coordinator United Nations Environment Programme Nairobi, Kenya

Dear Ms. Luque,

I am pleased to inform you that I have endorsed the full-sized project proposal detailed below:

| Decision Sought:       | CEO Endorsement of Full-sized Project  |
|------------------------|--|
| GEFSEC ID:             | 10526  |
| Agency:                | UNEP   |
| Agency ID:             | 01812  |
| Focal Area:            | Chemicals and Waste  |
| Project Type:          | Full-sized Project   |
| Country:               | Mexico   |
| Name of Project:       | Eliminate Mercury Use and Adequately Manage Mercury and Mercury<br>Wastes in the Chlor Alkali Sector in Mexico |
| GEF Project Financing: | \$12,000,000   |
| Agency Fee:            | \$ 1,080,000   |
| Funding Source:        | GEF Trust Fund   |
|                        |  |

| Agency F | ee Commit | ment:            |                               |                     |           |
|----------|-----------|------------------|-------------------------------|---------------------|-----------|
|          | Trust     | 20% committed at | 50% to be committed           | 30% to be committed | Total     |
| Agency   | Fund      | (US\$)           | at 1st Disbursement<br>(US\$) | (US\$)              | (05\$)    |
| UNEP     | GEFTF     | 216,000          | 540,000                       | 324,000             | 1,080,000 |

I am endorsing this project based on the understanding that the project is in conformity with the GEF focal areas strategies and in line with GEF policies and procedures.

Sincerely Moder

M.Sc. Carlos Manuel Rodríguez Chief Executive Officer and Chairperson

Copy to: Country Operational Focal Point, GEF Agencies, Trustee

1818 H Street, NW • Washington, DC 20433 • USA Tel: +1 (202) 473 3202 - Fax: +1 (202) 522 3240 E-mail: gefce@(thegef.org www.thegef.org **PROJECT:** Eliminate the use of mercury and properly manage mercury and mercury waste from the chlor-alkali sector in Mexico (GEF ID 10526)

#### **Objective of the project:**

"Reduce the negative impacts of mercury and mercury residues from the chlor-alkali sector on human health and the environment in Mexico".

CloroSur

GEF financing: USD 12,000,000

Co-financing: USD 129,500,000 Project duration: 2023-2027 (5 years)GEF Implementing Agency: UNEP Executing Agencies: IPA(In Due Diligence Contract Process), Centro Mexican para la Producción más Limpia.

**NEXT STEP. Project Implementation.** 

## **GLOBAL ENVIRONMENTAL BENEFITS (GEB)**

- Greenhouse gas emissions reduction: 43,186 tons of CO2 per year.
- Reduction, elimination and avoidance of chemicals of global concern: 150 tons of mercury.
- Direct beneficiaries: 15,000 people



![](_page_24_Picture_5.jpeg)

## GEF BUDGET \$ US.

| BUDGET BREA | AKDOWN US   | DOLLARS     |              |                   | AMOUNT     | %    |
|-------------|-------------|-------------|--------------|-------------------|------------|------|
|             |             |             |              |                   |            |      |
| EQUIPMENT,  | CYDSA PERS  | ONAL SUPPOI | RT (PROJECT, | <b>OPERATION)</b> | 7,882,619  | 66%  |
| CONSULTORI  | AS, CONSULT | ANCY, ADVIC | E            |                   | 1,861,000  | 16%  |
| TRIPS       |             |             |              |                   | 238,500    | 2%   |
| SEMINARS, T | EAMS, WORK  | SHOPS, PUBL | ICATIONS     |                   | 1,446,481  | 12%  |
| MANAGEMEN   | NT COST     |             |              |                   | 571,400    | 5%   |
|             |             |             |              |                   |            |      |
|             |             |             | TOTAL        |                   | 12,000,000 | 100% |

![](_page_25_Picture_2.jpeg)

## IQUISA NEW PLANT COATZACOALCOS PROJECT (Localization)

#### **IQUISA New Plant Localization**

IQUISA s New Chlorine & Caustic Plant Localization at Coatzacoalcos City Veracruz, México

![](_page_26_Figure_3.jpeg)

![](_page_26_Picture_4.jpeg)

![](_page_26_Picture_5.jpeg)

## Background

Current Mercury plant dates back from the **60s** and since then it has been operating, constantly updating itself technologically to maintain a profitable, safe and environmentally acceptable operation.

The New Membrane Membrane Plant will replace the Plant operating with mercury technology

The technological change will take place on the same site where the plant is currently operating, seeking synergies to take advantage of existing services and processes.

The initial annual production capacity will be **100,000 tons** and in the future it will be increased to **150,000 tons of Chlorine** 

Preliminary investment of close to **120 million dollars** is estimated in its first stage and **30 million dollars** for the second stage.

![](_page_27_Picture_6.jpeg)

## **Project execution**

- The Basic and Detail Engineering for Chlorine plant were done by BCMC (BLUE STAR BEIJING MACHINERY LTD). under. IQUISA review and supervise this Engineering processes.
- Site Construction is also managed, supervised and controlled by BCMC WITH Chinese Personal at Site and Its CONIP subcontractor and also IQUISA review and supervise this construction activities.
- All the utilities and services required for Plant operation were under IQUISA's scope including Engineering work & Construction. All Engineering designs were contracted with specialized Mexican firms.
- Also for all the project. IQUISA organized a multidisciplinary team with its technical staff and an external engineering firm (outsourcing) for the design review, supervision, administration / control including quality assurance.

**Cloro**Sur

## **Technical & Engineering Design**

- IQUISA as Chlorine Institute Member (CI), the Chlorine plant design was made according technical recommendations and statements. (Technical Pamphlets).
- The Engineering design was done according with current and applicable Mexican norms, USA and International codes and standards for the different involved project disciplines works such as; Foundation, civil, architectural, mechanical, piping, electrical, instrumentation and control.
- Risk analysis is also an important issue to take into account during the design and operation of our chemical plants and has the objective of identifying, mitigating, preventing and controlling them in our processes, developing the following activities:
  - HAZOP (Hazardous Operability) ANALYSIS.
  - SIL (Safety Integrity Level) LEVEL II.
  - Emergency Shut down System (ESD).
- Also modern Engineering Tools were applied for project design and control like; 3D and MS Project.

![](_page_29_Picture_8.jpeg)

# **Environmental Aspects.**

 $\bigcirc$ 

 $\bigcirc$ 

- It is fulfilled in advance the period stablished by UNEP to eliminate the use of Mercury (phase out 2025) in the production of Chlorine-Soda agreed in the Minamata Convention.
- It should be emphasized that this project will reduce Carbon Dioxide emissions to the atmosphere by a minimum amount of **43,186 TPA**, derived from the lower consumption of Electric Power.
- Use of the Hydrogen produced in the electrolyzers, replacing 90 % the use of natural gas in the boiler for the production of steam reducing greenhouse gas emissions with an atmospheric positive impact water vapor emissions instead CO2.
  - Use of Membrane Technology is clean and sustainable and friendly Environmental Process.
- Mercury not will be use anymore, removing Emissions and generation of Toxic and dangerous Wastes that need a special Sound Storage.

**Cloro**Sur

• Electricity consumption saving of 33 %.

## **GENERAL VIEW PLANTA LAY OUT.**

![](_page_31_Picture_1.jpeg)

![](_page_32_Picture_0.jpeg)

![](_page_32_Picture_1.jpeg)

![](_page_33_Picture_0.jpeg)

![](_page_34_Picture_0.jpeg)

![](_page_35_Picture_0.jpeg)

![](_page_36_Picture_0.jpeg)

# **GRACIAS iiiiiTHANK YOUiiiiii**.